# How to Develop a CLT Project









# **Copyright Materials**

This presentation is protected by US and International Copyright laws. Reproduction, distribution, display and use of the presentation without written permission of the speaker is prohibited.



MGA | Michael Green Architecture

















## **Program Education Credit Information**

Canadian Wood Council, Wood *WORKS!* and the Wood Solutions Fair is a Registered Provider with The American Institute of Architects Continuing Education System. Credit earned on completion of this program will be reported to CES Records for AIA members who complete a participation form at the registration counter. Certificates of Completion for non-AIA members are available on request.

This program is registered with the AIA/CES for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product. Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.









# **CLT Project: Architectural Concepts**

#### Michael Green

MGA | Michael Green Architecture www.mg-architecture.ca






CROSS LAMINATED TIMBER

CLT  $40' \times 10'$  (12 x 2.4)





# CLT

#### THE OPPORTUNITIES

LARGE FORMAT
FAST CONSTRUCTION
EXCELLENT SPAN TO THICKNESS
LOW WEIGHT
REDUCED FOUNDATION COSTS
SYSTEMS INTEGRATION
PRE-FABRICATED APPROACH
CARBON SEQUESTRATION
COMPETITIVE WITH CONCRETE
EXCELLENT FIRE PROPERTIES


# CLT

THE CHALLENGES

DETAILING
FIRE RATINGS
FLAME SPREAD RATINGS
ACOUSTIC PERFORMANCE
MOISTURE
PENETRATIONS
ENVELOPE DETAILING




## Charring



### **Charring Diagram**


- Char layer
- 2 Pyrolysis zone
- Normal wood




### **Charring Structural Design Diagram**

- Sacrificial layer (char layer and pyrolysis zone; no structural capacity)
- Residual section (structural capacity retained)
- 3 Rounded corner

## Charring and Encapsulation




## **Hybrid Charring and Encapsulation Details**




- Fire exposed side 2 layer LVL or LSL
- \*\*/\*\*\*Sacrificial DM, or LSL layer (2HR FRR)

#### Assembly illustrating charring only concept




- \*\*Wall-sacrifical DVL or LSL (2HR FRR) Ceiling: 2 layer 5/8" type X gypsum board (2HR FRR)
- Assembly illustrating hybrid charring and encapsulation concept



- Fire exposed side 2 layer LVL or LSL
- ""Sacrificial UVL or LSL layer + 1 layer 5/8" type X gypsum board (2HR FRR)

#### Assembly illustrating hybrid charring and encapsulation concept




- 2 layer 5/8" type X gypsum board (2HR FRR) Assembly illustrating encapsulation only concept

2 layer LVL or LSL

- 2 layer LVL or LSL \*\*Ceiling: sacrifical LVL or LSL (2HR FRR) Walt-2 layer 5/8" type X gypsum board (2HR FRR)
- Assembly illustrating hybrid charring and encapsulation concept
- Charring rates vary depending on moisture, density, species etc. The charring rate of 0.635mm/min is the generally accepted average. Refer to page XX for additional information on charring
- Interior firesh: exposed wood paneling subject to flame-spread rating and smoke developed classification code requirements. Refer to page 106 for additional information on flamespread, smoke classification and interior Trishes.

#### **Typical Details**





	Cast in place concrete floor (2HK FKK)			
2	Cast in place concrete wall (2HR FRR)			
3	Finish floor			
4	Finish ceiling			
5	Finish wall			
8	Facade (non-combustible)			
7	Pot light			
8	Sprinkler (plastic pipe)			
9	Electrical outlet			
10	Exhaust penetration with fire stopping			

ton ton a	annesste tower	diane and	second annuals.	n at exterior wall

1	2 layer LVL or LSL + 2 Layer 5/8" type X gypsum board underside only (2HR FFR)	9	Sprinkler (plastic pipe)
2	2 layer LVL or LSL + 2 Layer 5/8" type X gypsum board interior side only (2HR FFR)	10	Electrical outlet
3	Finish floor	11	Exhaust penetration with fire stopping
4	Finish ceiling	12	2" loose mineral wool insulation for sound absorption (ceiling)
5	Finish wall	13	2" loose mineral wool insulation for sound absorption (wall)
8	Facade (non-combustible)	14	Airspace to reduce sound transmission between floor and wall
7	Steel beam	15	Gap between drywall and stud to reduce sound transmission
8	Pot light		


Tall wood case study floor and wall section at exterior wall






Spandrel glass panel Spanitrel glass panel or nun-combustible clading

Typical concrete tower curtain wall facade section




- 2 layer LVL, LSL or CLT + 2 layer S46" type X gypsum bland (SHR FRR) Citalant cdiumn + 2 layer S46" type X gypsum bland beyond (SHR FRR) Citalam beam + 2 layer S46" type X gypsum bland (SHR FRR)
- Vision glass
- Spondrel glass panel Spondrel glass panel or non-combustible cladding

Tall wood case study curtain wall facade section (option 1 + 2)



- Concrete wall (2HR FRR) Non-contiustible cladding + rainscreen
- Typical concrete tower facade section




2 layer DAL, USL or CLT + 2 layer S/R\* type X gapman board CHRLF 2 layer DAL, USL or CLT + 2 layer S/R\* type X gapman board CHRLF

Non-combustible cliabling + reinscreen


Tall wood case study facade section (option 3 +4)

#### **Typical Details**



- Cast in place concrete floor (2HR FRR) Balcony door Finish floor


- Finish ceiling
- Finish floor balcony (sloping with waterproofing) Exposed concrete
- Pot light Sprinkler
- Spandrel panel + exhaust
- Typical concrete tower sliding door section at balcony



- 2 layer LVL or LSL + 2 Layer 5/8" type X gypsum board underside only (2HR FRR) Balcony door Finish floor
- Finish ceiling
- Finish floor balcony (sloping waterproafing)
- Exterior soffit
- Concrete topping and curb (2HR FRR)
- Steel beam
- Pot light
- 10 11 12 Sprinkler
- Drykead sprinkler with sleeved fire stopping (for balconsies up to 10' outboard) 2" loose mineral wool insulation for sound absorption

Tall wood case study sliding door section at balcony

#### **Typical Details**



- Cast is place concrete floor (2HR FRR)
- Double steel stud wall with 5/8" gypsum board on both sides
- Finish floor
- Finish ceiling
- Electrical outlet
- Put light
- Sprinkler
- Air space between walls to reduce sound transmission
- Mineral wool insulation for seend absorption

- 2 layer LVL or LSL + 2 Layer 5/8" type X gypoun board on underside only (2MR FRR) Double sheel shad wall with 5/8" gypsum board on both sides
- Finish floor
- Finish ceiling
- Electrical outlet
- Pet light
- Sprinkler
- Duct
- Air space between walls to reduce sound transmission
- 10 Mineral wool insulation for sound absorption
- 11 2" loose mineral wool insulation for sound absorption

Tall wood case study typical non-load bearing interior partition between units

## HISTORY

FIRE MASS APPROACHES

VANCOUVER BC











### MGA OFFICE

VANCOUVER BC

MGA | MICHAEL GREEN ARCHITECTURE VANCOUVER | NEW YORK









### **CANNON POINT HOUSE**

**NEW YORK** 

MGA | MICHAEL GREEN ARCHITECTURE VANCOUVER | NEW YORK











## RENDEZVOUS LODGE | WHISTLER BLACKCOMB







RONALD MCDONALD HOUSE
















HILLCREST VILLAGE 2012-030

## MGA









### WORLD'S TALLEST

VANCOUVER BC

MGA | MICHAEL GREEN ARCHITECTURE VANCOUVER | NEW YORK



# **CLT: Engineering Concepts**


**David Moses, Principal** 

PhD, PEng, PE, LEED® AP
Moses Structural Engineers Inc.

# Cross-laminated Timber (CLT)

Introductory Article (pdf) at:

www.mosesstructures.com



Source: FPInnovations

# **CLT Handbook**





www.FPInnovations.ca

## **APA Standard PRG-320**


- Standard for Performance-rated Cross-laminated timber
- Released in 2011
- Deals with tolerance, wood and adhesives, layups, manufacturing, quality assurance

## Canadian Codes and Standards

Not yet

# Things to consider when designing

- Available panel sizes, layups, thicknesses
- Looks for opportunities to maximize panel size (2-span, 3-span)



Moses Structural Engineers, R&D

# Things to consider when designing

- Available panel sizes, layups, thicknesses
- Looks for opportunities to maximize panel size (2-span, 3-span)
- Mix systems: concrete, steel, masonry, wood, glulam

# Design

- Roofs: Deflections tend to control design
- Floors: Vibration and deflections tend to control
- Walls: full CLT, glulam posts, CLT infill

## Connections

- Beam pockets on CLT walls
- Screws: different manufacturers (see trade show)
- Configurations: CLT Handbook examples







## Rules of Thumb

Courtesy: Equilibrium Consulting Inc., Vancouver
CLT Symposium 2011

- CLT design has the 'feel' of concrete
- Floor span-to-depth ratios 20-30
- Roof span-to-depth ratios 30-40
- Deflection and vibration control design(not strength)
- Engineers must consider creep and rolling shear
- Effective stiffness increases for longer spans

# **CLT:** Installation Concepts

### **Michael Krans**

Timmerman Timberworks www.timmermantimberworks.com

# From Paper to Panel

### A Brief Summary of the CLT Installation Process

- Introduction
- The Shop Drawing process
- The Site Survey process
- Notes on Logistics

# **Shop Drawing Process**

- Receipt of IFCs
- Decision: preliminary layout submittal vs. submittal of full, sealed shop drawings
- Factors: complexity of project and detail of IFC set
- Pros & Cons: preliminary layout submittal reduces reengineering time, covers off issues of liability/responsibility, but consumes time and resources
- Shop drawings vs. individual panel drawings—the manufacturing difference

# The Shop Drawing Process

- The proliferation of BIM/3 dimensional modeling software—and its effect on pre-fabrication
- Revit, AutoCAD, Solidworks, CADworks
- Interchange of models via FTPs, dropboxes etc
- A "Brave New World" in every sense of the phrase

# The Site Survey Process

- The reality interface—wood meets world
- Survey as state-of-the-art and seat of the pants
- State-of-the art: robotic Total Station c/w Bluetooth technology
- Next: 3 dimensional scanning systems (Faro etc)?
- Seat of the pants—get up there and measure . . .
- Last but not least, the survey as survey
- Putting the survey to paper—incorporating results, soliciting approvals

# **Notes on Logistics**

- Typical sizes—and weights
- Measure twice cut once
- Movement is money
- Movement means damage
- Integration of Logistics Chain from glue up, to fabrication, to delivery, to installation
- Implementation of tools, tricks, and strategies to make it look easy

# **CLT:** Supply Concepts

### **Patrick Chouinard**


Structurlam Products Ltd. www.structurlam.com




**UBC Earth Science Building** 




**UBC Earth Science Building Canopy** 





**UBC Earth Science Building** 



**Elkford Community Centre** 











**Elkford Community Centre** 



**UBC Bioenergy Research & Demonstration Facility** 






**UBC Bioenergy Research & Demonstration Facility** 



**Wayne Gretzky Sports Centre** 



**Wayne Gretzky Sports Centre** 

### CrossLam (CLT) Basics

- 2 x 6 SPF (Standard)
- Two types: Visual and Non-Visual
- Max sizes: 8' x 40' (V) 10' x 40' (NV)
- Available in 3,5,7,9 laminate layers
- Thicknesses from 99 309 mm (3.9" 12.17")
- CLT ANSI/APA PRG 320 Compliant
- Optional D. Fir Visual layer







**Douglas Fir Visual Layer** 

### The process for acquiring CrossLam

### Design

Interactive 3D model design using Digital Project, CadWorks, Revitt



Panel List
Billet List
Connection
Details

### Fabricate


Lap Joints
Window &
Door Openings
Beam Pockets

### Finish

Plane Hand Sand Number Wrap




Skills, knowledge & experience with CLT projects











BILLET AREA: 2560.00 PANEL AREA: 1961.82 WASTE: 23.37%

### The process for acquiring CrossLam

### Design

Interactive 3D model design using Digital Project, CadWorks, Revitt



Panel List
Billet List
Connection
Details

### Fabricate


Lap Joints
Window &
Door Openings
Beam Pockets

### Finish

Plane Hand Sand Number Wrap




Skills, knowledge & experience with CLT projects











**Cross Laminated Timber Design Guide** 


#### Structurlam Products Ltd Budget Pricing for CrossLam (Cross Laminated Timber Panels) CDN\$

			1	2	3			
Panel	# of	Panel	Blank Panel	Hand Framing (Floor/Roof)	5 Axis Robotic Framing (Walls)	Fasterner, Hardware, Shop Drawings		Visual Grade
Туре	Laminations	Thickness	\$/Sq. Ft	\$/Sq. Ft	\$/Sq. Ft	Floor/Roof \$/Sq. Ft.	Walls \$/Sq. Ft.	\$/Sq. Ft
SLT3	3	99mm	5.80	6.05	7.02	2.50	3.00	1.00
SLT5	5	169mm	9.68	9.93	11.21	2.50	3.00	1.00
SLT7	7	239mm	13.77	14.02	15.93	3.00	3.50	1.00
SLT9	9	309mm	17.53	17.97	19.90	3.00	3.50	1.00

Note: it's columns 1 or 2 or 3... not 1 + 2 or 1 + 3 or 1 + 2 + 3

















13,000 sq. ft. South Plant CLT Extension











# **Questions/ Comments?**

This concludes the:

American Institute of Architects
Ontario Association of Architects

Continuing Education Systems Program

How to Develop a CLT Project









## **MGA**



#### **Michael Green**

MGA | Michael Green Architecture
T: 604.336.4770
E: hello @ mg-architecture.ca
mg-architecture.ca



#### **Michael Krans**

Timmerman Timberworks T: 705.721.8916

E: mike@timmermantimberworks.com
Timmermantimberworks.com

#### **David Moses**

Moses Structural Engineers Inc.
T: 416-255-3337
E: dmoses@mosesstructures.com
Mosesstructures.com



#### **Patrick Chouinard**

Structurlam Products Ltd.
T: 647-467-6070
E: pchouinard@structurlam.com
Structurlam.com













### Full-scale Fire Test Results

### Walls

- 3-plys (114 mm) protected + 2 x ½" Drywall : 106 min
- 5-plys (105 mm) unprotected: 57 min
- 5-plys (175 mm) unprotected : 113 min

### **Floors**

- 3-plys (114 mm) protected + 2 x ½" Drywall : >77 min\*
- 3-plys (105 mm) + ¾" Drywall : 86 min
- 5-plys (175 mm) unprotected: 96 min
- 5-plys (175 mm) + ¾" Drywall : 124 min (≈ 2 hrs !!!)
- 7-plys (245 mm) unprotected : 178 min (≈ 3 hrs !!!)

<sup>\*</sup> Test has been stopped due to safety concerns. Failure has not been reached.